



NSC15000-ULT

AG-CHILL 15 Ton Air Cooled Ultra Low Temp Chiller (Qty 3 NSC5000-ULT in Parallel)





AG-Optimists, LLC 3130 South 1030 West, Suite 1 Salt Lake City, UT 84119 (541) 610-6858 www.ag-chill.com All Information Is For Reference Only









NSC15000-ULT

Standard Features and Benefits					
Performance	Working Temperature Range	-112°F(-80°C) to 70°F(21°C)			
	Temperature Stability	1	±2		
	Cooling Capacity at 70F	-94°F (-70°C) - 108,600 BTU/hr (31,830 Watts) -55°F (-48.3°C) - 182,900 BTU/hr (53,600 Watts)			
		-43.6°F (-42°C) - 194,700 BTU/hr (57,060 Watts)			
	Ambient Temperature (Standard)	40°F - 100°F			
	Pump Performance	0 GPM @ 44 PSI			
		135 GPM @ 40 PSI			
		270 GPM @ 26 PSI			
User Interface	Controls	Electronic Programmed Temperature Controller (PLC) with Constant (Setpoint & Process) Temperature Readout			
	Additional Features	Fluid Level Indicator, Touch Screen Controls			
Refrigeration Circuit	Compressor	Copeland Discus			
	Heat Exchanger	Brazed Plate Heat Exchanger			
	Refrigerant	R508B			
	Additional Features	Access Ports, Service Valves, Filter Drier, Sight Glass, Liquid Receiver, Thermostatic Expansion Valve (TXV), Oil Separator			
	Max Heat Rejection	120,000 BTU/hr (35.1 kW)			
Process Fluid	Pump	Continuous Duty, 15 HP Centrifugal Pump			
	Inlet/Outlet	2" NPT			
Circuit	Reservoir	80 Gallon Stainless Steel			
	Additional Features	Inline Strainer, Inlet and Outlet Temperature Sensors, Pump Discharge Pressure Transducer			
Construction	Frame	Galvanized Steel			
	Enclosure	Powder Coated Steel Enclosure with Easy Access Panels			
	Warranty	1 Year Stand	ard Warranty		
Quality	UL/CSA Certified (Full Assembly)	Certified for Outdoor Use ETL 3170655, UL STD 61010-2-011, CAN/CSA STD, C22.2 No. 61010-2-011			
	Manufacturing	Manufactured in the U.S.A. Certified ISO 9001:2015 Company			
Power	Available Voltages	Max Amps (FLA)	Recommended Breaker/Service (MCA)		
	480VAC / 3P / 60Hz (STANDARD)	80.1 Amps (std)	94.2 Amps (std)		

Optional Upgrades					
UPGRADES	Process Heating UL/CSA Outdoor Certified Extended Ambient (-15°F)	External Temperature Monitoring Alternate Pumps	Controller Auto Start Remote Start Crating		
	More Options and Customization Available - Contact Factory for More Information				

AG-Optimists, LLC

All Information Is For Reference Only







3130 South 1030 West, Suite 1 Salt Lake City, UT 84119 (541) 610-6858 www.ag-chill.com